

**IOSCO COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

004 2000

For corners in

IOSCO
(County)

Located In:

Corner Code #

1. Public Land Survey

T22N R 5E K-4

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

STATE OF MICHIGAN
IOSCO COUNTY
FILED
4-2000
3 JAN 0 4:04 P.M.
RONITA M. DOYLE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, William J. Rigg, in a field survey on August, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		19		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1844 +/- GLO Survey
12" W. Pine S40W 12 lks
6" Maple S65E 27 lks

1977 LCRC by Richard Miller. Found 1/2" pipe

ACCEPTED BY THE IOSCO COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 10-13-99

James H. Granger


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" pipe per previous survey by Richard Miller 1.54 ft. North of proportionate distance and on approximate line between K3 and K5..

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted position of 1/2" pipe and replaced with 5/8" rebar and remonumentation cap.

N 45° E 59.23' (R= 59.40') SW corner of House (Field Stone)
S 60° E 55.95' (R= 59.90') NW leg of Electrical Tower
N 45° W 47.30' Fence Corner
S 50° W 65.65' Fence Corner



Signed by William J. Rigg P.S.
Surveyor's Michigan License No. 41108

Date Dec. 27, 99

SECTION