

FEB 18 1999

98-40

SECTION

IOSCO COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
IOSCO COUNTY
FILED

8 DEC 98 1:15 P.M.

RONITA H. COYLE
REGISTER OF DEEDS

For corners in

<u>Iosco</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>22R</u> 5E	<u>K-5</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William J. Rigg in a field survey on Oct. 1, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1844+/- GLO SURVEY
12" Beech S43E 23 lks.
10" Beech S54W 27 lks.

ACCEPTED BY THE IOSCO COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 74 OF 1970 AT A MEETING HELD ON 9-22-98

James H. Geanger

1977 Found 1/2" pipe per LCRC by Richard Miller

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found and held 1/2" pipe as found and accepted by Richard L. Miller, in 1977 and recorded in LCRC 77-9.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1998 Remonumentation by William J. Rigg, #41108

Found 1/2" pipe and replaced with a 5/8" rebar with Remon Cap.

S45W 83.3' Power Pole
N55W 99.44' SE Cor. Church
N88E 32.29' 10" Elm
S25E 126.45' Elm Cluster of 6



Signed by *William J. Rigg*
Surveyor's Michigan License No. #41108

Date Nov. 10, 1998