

FEB 16 1999

90-43

SECTION

IOSCO COUNTY REMONUMENTATION CORNER  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
IOSCO COUNTY  
FILED

8 DEC 98 1:15 P.M.

BONITA M. COBLE  
REGISTER OF DEEDS

For corners in

<u>Tosco</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T22NR5E	K-6
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, William J. Rigg in a field survey on Oct 1, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1844+/- GLO SURVEY  
12" Birch W. 32 lks.  
14" Hemlock N42E 22 lks.

ACCEPTED BY THE IOSCO COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 74 OF 1970 AT A MEETING HELD ON 9-22-98

*James H. Granger*

1997 1/2" pipe per survey by Herbert J. Kobs

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" pipe as shown on survey by Herbert J. Kobs, #14097 done in 1997 and recorded in Liber 530, Page 82. Held pipe position as found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1998 Remonumentation by William J. Rigg, #41108

Fnd 1/2" pipe and replaced with a 5/8" Rebar with Remon Cap.

- N45W 46.88' Pine
- S45W 56.37' Power Pole
- N45E 44.01' Fence Corner
- S45E 37.03' Fence Corner



Signed by *William J. Rigg*  
Surveyor's Michigan License No. #41108

Date Nov 10, 1998