

**IOSCO COUNTY REMONUMENTATION CORNER**

LAND CORNER RE-ESTABLISHMENT CERTIFICATE  
Filing Reg. Act of Act 74, Mich. P.A. 1970

008 2000

For corners in

IOSCO

(County)

Located In:

Corner Code #

1. Public Land Survey

T22NR SE

K-8

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

2. Property Controlling in Section

S \_\_\_ T \_\_\_ R \_\_\_

S \_\_\_ T \_\_\_ R \_\_\_

3. Miscellaneous Property in Sec.

S \_\_\_ T \_\_\_ R \_\_\_

S \_\_\_ T \_\_\_ R \_\_\_

STATE OF MICHIGAN  
IOSCO COUNTY  
FILED  
8-2000  
3 JAN 0 4:03 P.M.

MURIEL H. DOYLE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, William J. Rigg, in a field survey on August, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1844 +/- GLO Survey 12" Cedar S80E 4 lks, 10" Cedar N43W 21 lks
- 1974 Survey by Richard Miller references corner.
- 1974 Survey by James Campbell found and accepted 1/2" rod w/cap.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Found and accepted position of 1/2" bar per previous surveys by Richard Miller and James Campbell.

ACCEPTED BY THE IOSCO COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 10-13-99  
*James H. Granger*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 1/2" bar and replaced with 5/8" rebar and remonumentation cap.

- N40W 61.35' Power Pole
- N35E 92.4' 8" Birch
- S45W 77.9' 6" Elm
- S45E 54.6' Fence Post



Signed by William J. Rigg P.S.  
Surveyor's Michigan License No. 41108

Date Dec 27, 99

REF  
2000  
SECTION