

FEB 15 2001

SECTION

IOSCO COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

015 2001

STATE OF MICHIGAN
IOSCO COUNTY
FILED

13 FEB 2001 9:21:24 AM

BONITA W. COYLE
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

For corners in

IOSCO

(County)

Located In:

Corner Code #

1. Public Land Survey

T 22N R 3E K-9

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, William J. Rigg, P.S., in a field survey on October 12 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
1844 +/-, GLO Survey, set post, 8" Hemlock, S89.5W .02 lks, 8" Fir, N70W .14 lks

1950 MDOT Highway Maps

1974 James G. Campbell, Found 3/4" Bolt, Liber 235, Page 359

1975 James G. Campbell, Found 3/4" Bolt, Liber 248, Page 243

1986 Timothy L. Lapham, Found 3/4" Bolt, See LCRC 86-01

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Found 3/4" bolt as evidenced, witnesses check.

ACCEPTED BY THE IOSCO COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER P.A.
345 OF 1990 AT A MEETING
HELD ON 10-11-2000

James H. Stanger

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Replace 3/4" bolt with 5/8" rerod and Remon Cap
- N45E - SE Corner concrete head wall - 30.25'
- N45W - SW Corner concrete head wall - 28.15'
- South - Center line of pavement, M-55 - 57.35'
- S6W - 123.60 Dead End Sign
- S12E 100.20' Towerline Road Sign



Signed by

William J. Rigg, P.S.

Surveyor's Michigan License No. #41108

Date December 22, 2000