

FEB 16 1999

IOSCO COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

98-42

SECTION

For corners in

<u>Iosco</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>22NR5E</u>	<u>L-3</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN
IOSCO COUNTY
FILED
8 DEC 98 1:15 P.M.
BONITA M. COYLE
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William J. Rigg, in a field survey on Oct. 1, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1838+/- GLO Survey
24" W. Pine N11E 26 lks.
12" Maple S84W 14 lks.

ACCEPTED BY THE IOSCO COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER P.A.
74 OF 1970 AT A MEETING
HELD ON 9-22-98

James H. Gieringer


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found no evidence of original corner or re-survey. Fence corner falls 2' North and 0.4' West of calculated position by using proportionate distance between K-3 and M-3. Held fence corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1998 Remonumentation by William J. Rigg, #41108

Nothing found, used fence corner as position.
Set 5/8" Rebar with Remonumentation Cap #41108
S85W 61.84' Maple Clump
S45E 93.64' 12" Oak
N45E 180.31' 10" Pine
N 5E 166.60' 6" Elm



Signed by William J. Rigg P.S.
Surveyor's Michigan License No. #41108

Date Nov. 10, 1998