

IOSCO COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDEMENT CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

OSHTON County  
1. Public Land Survey

Location in: 22ND SE Range 4-7  
T    R     
T    R     
T    R     
S    T    R     
S    T    R     
S    T    R     
S    T    R   

0:1 2000  
STATE OF MICHIGAN  
11-2000  
3 JAN 0 4:05 P.M.  
RONITA H. COVILL  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_


I, William J. Rigg, in a field survey on August, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1844 +/- GLO Survey  
10" Beech N82W 03 lks  
10" Beech S60E 63 lks



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" bar 2' +/- West of proportionate distance between K7 and M7 and held 1/2" Rebar.

ACCEPTED BY THE IOSCO COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 343 OF 1990 AT A MEETING HELD ON 10-13-99  
James H. Branger

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Remonumentation by William J. Rigg, #41108  
Accepted position of 1/2" bar and replaced with a 5/8" rebar with Remonumentation Cap.  
North 21.25' 14" Elm  
N20W 33.90' 10" Elm  
S50E 39.70' 12" Apple  
S5W 28.85' 10" Elm

Signed by William J. Rigg Date Dec 27, 1999  
Surveyor's Michigan License No. 41108

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983  
REVISED OCT., 1985

0:1 2000  
SECTION