

FEB 15 2001

SECTION

IOSCO COUNTY REMONUMENTATION CORNER  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

018 2001

For corners in

IOSCO  
(County)

Located In: Corner Code #

- 1. Public Land Survey T 22N R SE L - 9  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

STATE OF MICHIGAN  
IOSCO COUNTY  
FILED

13 FEB 2001 9:21:24 AM

BONITA M. COYLE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, William J. Rigg, P.S., in a field survey on October 12 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

- A. Description of original monument and accessories and/or subsequent restoration:  
1844 +/-, GLO Survey, set post, 14" Aspen, N12W 19 lks, 12" W. Pine, S5E 6 lks  
1986 Timothy L. Lapham, set 1/2" Rerod, See LCRC 86 - 01  
1986 Timothy L. Lapham, set 1/2" Rerod, Liber 345, Page 78

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" bar and cap as evidenced, witnesses check.

ACCEPTED BY THE IOSCO COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 10-11-2000

*James H. Changer*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Replaced 1/2" bar and cap with 5/8" rerod and Remon Cap
- N05E - Center line of North concrete R/W marker - 53.94'
- N09W - 14" Maple - 54.75'
- South - Center line of pavement, M-55 - 26.70'
- N65W - 83.92' Nail in P.P.
- S50E - 125.30' Nail in P.P.



Signed by *William J. Rigg, P.S.*  
Surveyor's Michigan License No. #41108

Date December 22, 2000