

**SURVEY & REMONUMENTATION**

FEB 16 1999

SECTION

**IOSCO COUNTY REMONUMENTATION CORNER  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

98-36

For corners in

Iosco	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>22N</u> R <u>5E</u>	<u>M-2</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

STATE OF MICHIGAN  
IOSCO COUNTY  
FILED

8 DEC 98 1:14 P.M.

BONITA M. COYLE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, William J. Rigg, in a field survey on Oct. 1, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- |      |   |      |   |
|------|---|------|---|
| 1838 | GLO Survey<br>6" W. Oak S74W 26 lks<br>13" Pine N43W 19 lks   | 1992 | LCRC's Survey by Kenyo J. Shellenbarger |
| 1931 | GLO RE-SURVEY<br>Fnd. Pine stump N43W 19 lks<br>4" W. Oak N23.75E 127 lks<br>8" W. Oak N46.75W 85 lks | 1995 | Herbert J. Kobs found Corner.           |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found and accepted GLO mon as shown on LCRC and surveys recorded by Keno J. Shellenbarger, #30101 and Herbert J. Kobs, #14097 in 1992 and 1995 respectively.


ACCEPTED BY THE IOSCO COUNTY  
SURVEY PEER GROUP AS THE  
OFFICIAL CORNER UNDER P.A.  
345 OF 1990 AT A MEETING  
HELD ON 9-22-98

*James H. Shellenbarger*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1998 Remonumentation by William J. Rigg #41108  
Fnd. GLO monument and held position.

- N25E 94.85' 3' Twin Oak
- N40W 56.50' 24" Oak
- S70W 76.54' Twin Oak
- S30W 127.47' Twin Oak



Signed by *William J. Rigg*  
Surveyor's Michigan License No. #41108

Date Nov. 10, 1998