

FEB 16 1999

IOSCO COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

98-45

STATE OF MICHIGAN
IOSCO COUNTY
FILED

8 DEC 98 1:20 P.M.

BONITA M. COYLE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

SECTION

For corners in

<u>IOSCO</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 22N R 5E	M-4 ✓
	T 22N R 6E	A-4
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William J. Rigg in a field survey on Oct. 1, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1838 GLO Survey
13" Maple S57W 6 lks.
10" Beech N42W 26 lks.
- 1931 GLO RE-SURVEY
12" W. Oak S10.75E 166 lks.
14" Maple N71.75W 117 lks.

ACCEPTED BY THE IOSCO COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER P.A.
375 OF 1990 AT A MEETING
HELD ON 9-22-98

James H. Cranger

1992 1" Square bar per LCRC & Survey by Keyno J. Shellenbarger

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Held corner as used and recorded by Keno Shellenbarger in 1992.
LCRC 92-6 & 92-7 and survey Liber 430, Page 450.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1998 Remonumentation by William J. Rigg #41108

End. 1" Square bar in Mon. box and replaced with 5/8 Rebar with Remon Cap.

- S45E 46.16' Fence Post
- N35W 65.49' Power Pole
- N60E 66.02' 8" Willow
- S30E 78.19' 8" Willow



Signed by William J. Rigg
Surveyor's Michigan License No. #41108

Date Nov. 10, 1998