

**FEB 15 2001**

**IOSCO COUNTY REMONUMENTATION CORNER  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

**SECTION**

For corners in

**IOSCO**

(County)

Located In:

Corner Code #

1. Public Land Survey

T 22N R 5E M-8 ✓

T 22N R 6E A-8

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling  
in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous  
Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

**006 2001**

STATE OF MICHIGAN  
IOSCO COUNTY  
FILED

13 FEB 2001 9:21:06 AM

RONITA M. COYLE  
Register of Deeds, Stamp & File Number  
REGISTER OF DEEDS

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, **William J. Rigg, P.S.**, in a field survey on **October 12 2000** do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:  
1844 +/-, GLO Survey, set post, 12" Hemlock, S37W 24 lks, 12" Hemlock, N87W 14 lks

1973 James G. Campbell, Set 5/8" Rod inside pipe, Liber 221, Page 932

1974 James G. Campbell, Found 2" Pipe with 5/8" rod inside, Liber 235, Page 359

1986 Timothy I. Lapham, Found 3/8" Rerod, Sec LCRC 86-05

1998 Herbert J. Kobs, Found 3/8" Rerod, Liber 547, Page 139

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/8" rod as evidenced, witnesses check.

ACCEPTED BY THE IOSCO COUNTY  
SURVEY PEER GROUP AS THE  
OFFICIAL CORNER UNDER P.A.  
345 OF 1990 AT A MEETING  
HELD ON 10-11-2000

*James H. Stranger*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replace 3/8" rod with 5/8" rerod and Remon Cap

S45W 46.38' Corner Post

N45W 47.28' Corner Post

N45E 37.98' Corner Post

S45E 51.97' Telephone Pedestal

Signed by *William J. Rigg*

Date December 22, 2000

Surveyor's Michigan License No. #41108