

FEB 18 1999

IOSCO COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

98-49

STATE OF MICHIGAN
IOSCO COUNTY
RECORD

8 DEC 98 1:20 P.M.

RONITA M. FOYLE
REGISTER OF DEEDS

SECTION

For corners in

| Inscoc (County) | Located In: | Corner Code # |
|---------------------------------------|-------------|---------------|
| 1. Public Land Survey | T 22N R 5E | M-3 |
| | T 22N R 6E | A-3 ✓ |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S T R | |
| | S T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

William J. Rigg, in a field survey on Oct. 1, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|---|----|---|----|---|----|---|----|---|----|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.


A. Description of original monument and accessories and/or subsequent restoration:

- 1844 GLO Survey 1974 LCRC references corner by James G. Campbell
- 14" Y. Pine S46W 26 lks
- 12" W. Pine N45W 14 lks
- 1940 GLO RE-SURVEY 1992 Raised 1/2" pipe with 1/2" rebar by Keyno J. Shellenbarger
- 6" W. Birch N56.5E 12 lks
- 5" Maple S54E 73 lks
- 6" Poplar N56W 75 lks 1995 Found 1/2" pipe per survey by Herbert J. Kobs

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fnd. pipe with raised bar and cap as recorded by Herbert J. Kobs, #14097, as recorded in 1995, Liber 514, Page 47.

ACCEPTED BY THE IOSCO COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER P.A.
745 OF 1990 AT A MEETING
HELD ON 9-22-98
James H. Kranger



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1998 Remonumentation by William J. Rigg #41108

Fnd. Pipe and raised bar w/cap and replaced with 5/8" rebar and Remon Cap.

- S54E 46.92' 20" Blazed Maple
- N80W 59.58' White Pine
- N30E 44.84' 24" Maple
- S40W 110.18' 12" White Pine

Signed by *William J. Rigg P.S.*
Surveyor's Michigan License No. #41108

Date *Nov. 10, 1998*