

SURVEY & REMONUMENTATION

DEC 13 1993

COMMISSION

**IOSCO COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Iosco</u> <small>County</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>6E</u>	<u>A-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

REGISTER OF DEEDS
 IOSCO COUNTY, MICH.
Barbara M. Coyle

DEC 1 11 06 AM '93

FILED
93-28

Register of Deeds Stamp & File Number

I, James H. Granger, in a field survey on November 15-17, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1838 Original Survey, Lewis Glason
 Set Wood Post
 14" White Birch S36°W 26 lks
 7" Beech N47°W 36 lks


1931 Dependent Resurvey, Guy Veal

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd. 1" pipe at intersection of E-W fence lines and road
Fd. 1931 witness: 38" willow tree - distance to pipe checks within 1'
Position accepted as most probable location of monument set in 1931 Dependent Resurvey.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" by 30" rod with 3" dia. alumin. cap
1931 witness: 38" Willow N15°W 124.4' (123.4'R)
Set nail & tag PS # 16041
 8" Ash N33°W 56.76'
 12" Ash S25°W 83.06'
 14" Ash S40°E 47.61'
 8" White Pine N48°E 50.77'



Signed by James H. Granger

Date Nov. 30, 1993

Surveyor's Michigan License No. 16041