

SURVEY & REMONUMENTATION

DEC 13 1993

COMMISSION

**IOSCO COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iosco (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>6E</u>	<u>A-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Dec 11 06 AM '93
REGISTER OF DEEDS
IOSCO COUNTY, MICH.
Donna M. Coyle

93-29
FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, **James H. Granger**, in a field survey on **November 15-17**, 19 **93**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1938 Original Survey, Lewis Clason
Set Wood Post
10" Maple S42°W 17 lks
12" Birch N76°W 40 lks

1931 Dependent Resurvey, Guy Veal
1985 Tim Lapham #27595

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd. 1/2" rerod with cap #27595
1985 witness deteriorated
position accepted as most probable location of monument set
in 1931 Dependent Resurvey

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" by 30" rod with 3" dia. alunm cap
2'± West of road centerline

Set nail and tag PS #16041 in:

- Fence Post N10°E 278.03
- Power Pole N60°W 219.43'
- Power Pole S45°W 318.99'
- Fence Post N80°E 34.60'



Signed by *James H. Granger*

Date **Nov. 30, 1993**

Surveyor's Michigan License No. **16041**