

SURVEY & REMONUMENTATION

IOSCO COUNTY REMONUMENTATION CORNER FEB 15 2001

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

IOSCO
(County)

Located In: Corner Code #

- | | | |
|------------------------------------|--------------------------|-----------|
| 1. Public Land Survey | T <u>22N</u> R <u>5E</u> | M - 8 / ✓ |
| | T <u>22N</u> R <u>6E</u> | A - 8 ✓ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

006 2001

STATE OF MICHIGAN
IOSCO COUNTY
FILED

13 FEB 2001 9:21:06 AM

RONITA M. COYLE
Register of Deeds, Stamp & File Number
REGISTER OF DEEDS

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William J. Rigg, P.S., in a field survey on October 12, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

- A. Description of original monument and accessories and/or subsequent restoration:
 1844 +/-, GLO Survey, set post, 12" Hemlock, S37W 24 lks, 12" Hemlock, N87W 14 lks
 1973 James G. Campbell, Set 5/8" Rod inside pipe, Liber 221, Page 932
 1974 James G. Campbell, Found 2" Pipe with 5/8" rod inside, Liber 235, Page 359
 1986 Timothy I. Lapham, Found 3/8" Rerod, See LCRC 86-05
 1998 Herbert J. Kobs, Found 3/8" Rerod, Liber 547, Page 139

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/8" rod as evidenced, witnesses check.

ACCEPTED BY THE IOSCO COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER P.A.
345 OF 1990 AT A MEETING
HELD ON 10-11-2000

James H. Stranger

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Replace 3/8" rod with 5/8" rerod and Remon Cap
- S45W 46.38' Corner Post
- N45W 47.28' Corner Post
- N45E 37.98' Corner Post
- S45E 51.97' Telephone Pedestal

Signed by *William J. Rigg, P.S.*
Surveyor's Michigan License No. #41108

Date December 22, 2000