

SURVEY & REMONUMENTATION

FEB 15 2001

**IOSCO COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

SECTION

For corners in

IOSCO

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|--------------------------|---------|
| 1. Public Land Survey | T <u>22N</u> R <u>5E</u> | M - 9 |
| | T <u>22N</u> R <u>6E</u> | A - 9 ✓ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

011 2001

STATE OF MICHIGAN
IOSCO COUNTY
FILED

13 FEB 2001 9:21:24 AM

BONITA M. COYLE
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, **William J. Rigg, P.S.**, in a field survey on **October 12, 2000** do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1844 +/-, GLO Survey, set post, 12" Birch, S63W 18 lks, 11" Birch, N13W 12 lks
- 1950 +/- MDOT Highway Maps
- 1973 James G. Campbell, Found bolt in mon box, Liber 227, Page 932
- 1974 James G. Campbell, Found mon box, Liber 235, Page 359
- 1975 James G. Campbell, Found rod in mon box, Liber 248, Page 243
- 1986 Timothy L. Lapham, Found rod in mon box, See LCRC 86-01
- 1986 Timothy L. Lapham, Found rod in mon box, See LCRC 86-02
- 1998 Herbert J. Kobs, Found boat spike in mon box, Liber 547, Page 139

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Found boat spike in mon box as evidenced, witnesses check.

ACCEPTED BY THE IOSCO COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 10-11-2000

James H. Kranger

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Replace boat spike with 5/8" rerod and Remon Cap
- S45E - 67.20' 10" Tamarack
- N20E - NE Corner E. concrete head wall - 69.5'
- N20W - NW Corner W. concrete head wall - 70.9'
- North - Center line of pavement, M-55 - 4.0'
- S40W - Telephone Pole - 81.80'



Signed by *William J. Rigg*
Surveyor's Michigan License No. #41108

Date December 22, 2000