

FEB 15 2001

IOSCO COUNTY REMONUMENTATION CORNER SECTION  
 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

IOSCO  
 (County)

Located In: Corner Code #

- |                                    |                          |          |
|------------------------------------|--------------------------|----------|
| 1. Public Land Survey              | T <u>22N</u> R <u>5E</u> | M - 12   |
|                                    | T <u>22N</u> R <u>6E</u> | A - 12 ✓ |
|                                    | T _____ R _____          | _____    |
|                                    | T _____ R _____          | _____    |
| 2. Property Controlling in Section | S _____ T _____ R _____  | _____    |
|                                    | S _____ T _____ R _____  | _____    |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____  | _____    |
|                                    | S _____ T _____ R _____  | _____    |

012 2001

STATE OF MICHIGAN  
 IOSCO COUNTY  
 FILED

13 FEB 2001 9:21:24 AM

BONITA M. DOYLE  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, William J. Rigg, P.S., in a field survey on October 12, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

| A  | B  | C | D  | E | F  | G | H  | I | J  | K | L  |
|----|----|---|----|---|----|---|----|---|----|---|----|
| 1  |    |   |    |   |    |   |    |   |    |   |    |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |
| 3  |    |   |    |   |    |   |    |   |    |   |    |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |
| 5  |    |   |    |   |    |   |    |   |    |   |    |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |
| 7  |    |   |    |   |    |   |    |   |    |   |    |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |
| 9  |    |   |    |   |    |   |    |   |    |   |    |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |
| 11 |    |   |    |   |    |   |    |   |    |   |    |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |
| 13 |    |   |    |   |    |   |    |   |    |   |    |

- A. Description of original monument and accessories and/or subsequent restoration:  
 1844 +/-, GLO Survey, set posst, 8" Hemlock, S44W 10 lks, 12" Aspen, N19W 17 lks  
 1986 Phillip D. Case, Set 1/2" Rerod in GLO position, See LCRC 90 - 13

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Rerod as evidenced, witnesses check.

ACCEPTED BY THE IOSCO COUNTY  
 SURVEY PEER GROUP AS THE  
 OFFICIAL CORNER UNDER P.A.  
 345 OF 1990 AT A MEETING  
 HELD ON 10-11-2000

*James H. Chandler*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Replace 1/2" rerod with 5/8" rerod and Remon Cap  
 N15E - 8" Red Pine - 20.28'  
 N57E - 10" Red Pine - 15.00'  
 S42W - 20" Maple in clump - 42.12'  
 S88W - 6" Maple - 50.26'



Signed by William J. Rigg  
 Surveyor's Michigan License No. #41108

Date December 22, 2000