

SURVEY & REMONUMENTATION

DEC 13 1993

IOSCO COUNTY REMONUMENTATION CORNER LAND CORNER RECORDATION CERTIFICATE

COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>IOSCO</u> (County)	Located In:	Corner Code ##
1. Public Land Survey	T <u>22N</u> R <u>6E</u>	<u>F-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REGISTER OF DEEDS
IOSCO COUNTY, MICH.

Richard L. Miller

93-10
NOV 24 4 31 PM '93

FILED

Register of Deeds Stamp & File Number

I, RICHARD L. MILLER, in a field survey on NOVEMBER 9, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1843 ORIGINAL SUBDIVISION MULLETT & BURT
SET WOOD POST
30" HEMLOCK S.48 E. 14 LKS
14" HEMLOCK N.76 W. 19 LKS

1931 DEPENDANT RESURVEY GUY VEAL, APPROVED 1933
SET 3 1/2" BRASS TABLET IN 6" DIAMETER CONCRETE CYLINDER, 24" LONG
6" MAPLE N.64 3/4 E. 131 LKS
6" BIRCH S.3 1/2 E. 109 LKS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

RESURVEY DEPENDANT CORNER MONUMENT DESTROYED BY ROAD CONSTRUCTION. DEPENDANT RESURVEY WITNESSES GONE. RESET POSITION USING FOUND EAST 1/4 CORNER MONUMENT SECTION 16 AND SOUTH-EAST CORNER MONUMENT SECTION 16 USING THE BEARING RELATIONSHIP AND PRO-RATED DISTANCE TO SOUTHWEST CORNER SECTION 16. CORNER IN EAST-WEST ROAD CENTERLINE, 3' EAST OF FENCE LINE SOUTH.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET MONUMENT CONSISTING OF 3 ALUMINUM DISC ATTACHED TO 5/8" RE-ROD 30" LONG PLACED 6" BELOW SURFACE. MARKED T.22N.-R.6E. 16 1/4 21
SET 3/4" PIPE IN EAST-WEST FENCE N.60 E. 46.84'
SET WITNESS TAG IN N.E. SIDE POWER POLE N.30 W. 73.25'
SET WITNESS TAG IN N.W. SIDE 4" CEDAR S.55 W. 37.30'
SET WITNESS TAG N.E. SIDE 6" MAPLE S.15 E. 34.45'

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		18		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Signed by *Richard L. Miller* Date NOVEMBER 17, 1993
Surveyor's Michigan License No. 16050

