

SURVEY & REMONUMENTATION

FEB 16 1999

REMONUMENTATION CORNER

98-35

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
IOSCO COUNTY
FILED

8 DEC 98 1:14 P.M.

MONITA M. COYLE
REGISTER OF DEEDS

For corners in

IOSCO (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>22NR 6E</u>	<u>I-13</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6		5		4		3		2		1
3											
4	7		8		9		10		11		12
5											
6	18		17		16		15		14		13
7											
8	19		20		21		22		23		24
9											
10	30		29		28		27		26		25
11											
12	31		32		33		34		35		36
13											

I, JAMES H. GRANGER, in a field survey on SEPTEMBER 29, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1837 (GLO) Lewis Clason Set Wood Post 11" Elm N18"E 9 lks
10" Elm N66"W 28 lks

ACCEPTED BY THE IOSCO COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER P.A.
345 OF 1990 AT A MEETING
HELD ON 9-22-98

James H. Granger

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Field measure to approx. location based on single proportionate measurement between SE corner Sec. 36 and NW cor. Sec. 2 T21N, R6E and found Irons at SW cor. Sec. 34 and NW cor. Sec. 3, T21N, R6E. No original evidence found. Evaluated distances on both sides of Township line to establish consistency with measured vs. recorded distances. Found nail does not fit proportionate distances nor closing corner offset from NW cor. Sec. 2. Establish. cor. location at 13.32' east of found nail and 14.52' west of NW cor. Sec. 2, T21N, R6E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" iron rod w/ remon cap @ centerline of Townline & W edge Sand lake Rd.

- Maple 36" dia. N20°E 129.54' nail & tag
- Maple 8" dia. N51°E 57.40' nail & flag
- Aspen 16" dia. S62°W 71.56' nail & tag
- W. Pine 18" dia. N57°W 89.43' nail & tag

Reмон Cap NW cor Sec. 2 East 14.52' T21N, R6E (I-1)



Signed by James H. Granger
Surveyor's Michigan License No. 16041

Date November 2, 1998