

SURVEY & REMONUMENTATION

DEC 13 1993

COMMISSION

**IOSCO COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

IOSCO (County)	Located In:	Corner Code ##
1. Public Land Survey	T <u>22N</u> R <u>6E</u>	<u>J-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

FILED
93-15
 NOV 24 4 32 PM '93
 REGISTER OF DEEDS
 IOSCO COUNTY, MICH.
Richard L. Miller

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5									●			
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, RICHARD L. MILLER in a field survey on OCTOBER 7, 1993 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1843 ORIGINAL SUBDIVISION MULLETT & BURT 1964 U.S.F.S. ROBERT A. GRIFFIN R.L.S. #13584
SET WOOD POST
8" SPRUCE N.64 E. 20 LKS
6" SPRUCE S.40 W. 19 LKS
 - 1931 DEPENDANT RESURVEY GUY VEAL, APPROVED 1933
SET 3½" BRASS TABLET IN 6" DIAMETER CONCRETE CYLINDER, 24" LONG
#1-6" W. OAK N.4½ E. 92 LKS
#2-9" W. OAK S.18¼ E. 108 LKS
#3-FENCE CORNER POST S.11 3/4 W. 280 LKS
#4-FENCE CORNER POST N.66½ W. 213 LKS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1931 MONUMENT IN ORIGINAL POSITION.
FOUND #1 WITNESS

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 3½" DIAMETER BRASS CAP IN 6" CONCRETE CYLINDER, 24" LONG, 4" ABOVE GROUND
- 10" DOCK SPIKE IN E. SIDE 16" W. OAK N.4½ E. 60.90' (1931 & 1964)
- SET WITNESS TAG IN N. SIDE 14" BALSAM N.89 E. 169.74' (1964)
- SET WITNESS TAG IN N.W. SIDE 10"-8" TWIN R. PINE S.30 W. 84.13' (1964)
- 10" DOCK SPIKE IN S.W. SIDE OF 12" R. PINE N.30 W. 119.65' (1964)
- SET WITNESS TAG IN EAST SIDE 12" B. OAK S.40 E. 68.30'



Signed by *Richard L. Miller* Date NOVEMBER 17, 1993
 Surveyor's Michigan License No. 16050