

**SURVEY & REMONUMENTATION**

DEC 13 1993

**IOSCO COUNTY REMONUMENTATION CORNER  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in \_\_\_\_\_

IOSCO (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>6E</u>	<u>K-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

**93-22**  
**FILED**  
 NOV 24 4 32 PM '93  
 REGISTER OF DEEDS  
 IOSCO COUNTY, MICH.  
*Richard L. Miller*

Register of Deeds Stamp & File Number

I, RICHARD L. MILLER in a field survey on OCTOBER 7, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

1843 ORIGINAL SUBDIVISION MULLETT & BURT  
SET WOOD POST  
10" SPRUCE S.02 E. 145 LKS

1931 DEPENDANT RESURVEY GUY VEAL, APPROVED 1933  
SET 3 1/2" BRASS TABLET IN 6" DIAMETER CONCRETE CYLINDER, 24" LONG  
#1-10" J. PINE N.46 1/2 E. 117 LKS  
#2-7" J. PINE S.45 E. 75 LKS  
#3-12" J. PINE S.20 1/2 W. 86 LKS  
#4-10" N. PINE N.43 3/4 W. 47 LKS

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

FOUND 1931 MONUMENT IN ORIGINAL POSITION 6" ABOVE GROUND.  
FOUND #4 1931 WITNESS  
CENTERLINE NORTH-SOUTH ROAD 48' WEST

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

3 1/2" DIAMETER BRASS CAP IN 6" CONCRETE CYLINDER, 24" LONG  
10" DOCK SPIKE IN S.E. SIDE OF 12" R. PINE N.71 E. 39.15' (1964)  
10" DOCK SPIKE IN S.W. SIDE OF 8" R. PINE S.10 E. 8.40' (1964)  
10" DOCK SPIKE IN S.W. SIDE OF 16" R. PINE N.43 3/4 W. 31.20' (1931 & 1964)  
SET WITNESS TAG IN N.W. SIDE OF 18" B. OAK S.40 W. 18.29'

Signed by *Richard L. Miller*  
Surveyor's Michigan License No. 16050

Date NOVEMBER 17, 1993

