

**SURVEY & REMONUMENTATION**

DEC 13 1993

COMMISSION

**IOSCO COUNTY REMONUMENTATION CORNER  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

REGISTER OF DEEDS  
IOSCO COUNTY, MICH

*Richard L. Miller*

NOV 24 4 32 PM '93  
**93-21**

FILED

For corners in

<u>IOSCO</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>6E</u>	<u>L-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, RICHARD L. MILLER in a field survey on OCTOBER 5, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

1843 ORIGINAL SUBDIVISION MULLETT & BURT  
SET WOOD POST  
20" HEMLOCK S.04 W. 10 LKS  
12" HEMLOCK N.43 E. 12 LKS

1931 DEPENDANT RESURVEY GUY VEAL, APPROVED 1933  
SET 3 1/2" BRASS TABLET IN 6" DIAMETER CONCRETE CYLINDER, 24" LONG  
14" N. PINE N.53 W. 84 LKS  
7" W. BIRCH S.33 1/4 E. 111 LKS

1964 U.S.F.S. ROBERT A. GRIFFIN R.L.S. #13584

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

FOUND 1931 MONUMENT IN ORIGINAL POSITION  
FOUND 1 1931 WITNESS  
FOUND 3 1964 WITNESSES

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

3 1/2" DIAMETER BRASS CAP IN 6" CONCRETE CYLINDER, 24" LONG, 6" ABOVE GROUND  
10" DOCK SPIKE IN N.W. SIDE 16" W. PINE N.36 E. 83.90' (1964)  
FOUND WITNESS TAG IN N.E. SIDE CORNER POST S.50 1/2 E. 62.96'  
10" DOCK SPIKE IN S.E. SIDE 12" MAPLE S.27 W. 38.60' (1964)  
10" DOCK SPIKE IN N.E. SIDE 38" W. PINE N.53 W. 55.20' (1931 & 1964)

Signed by *Richard L. Miller*  
Surveyor's Michigan License No. 16050

Date NOVEMBER 17, 1993

