

SURVEY & REMONUMENTATION

DEC 13 1993

COMMISSION

**IOSCO COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>IOSCO</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>6E</u>	<u>M-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, **JAMES H. GRANGER**, in a field survey on **NOVEMBER 15-17**, 19 **93**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1838 Original Survey Lewis Clason
Set Wood Post
7" Aspen N44°W 17 lks
8" Yellow Pine S45°W 30 Lks

1907 Howard Belknap, Co. Surveyor
1931 Dependent Resurvey Guy Veal
1964 USFS Robert Griffin #13584

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd. 3½" dia brass cap on conc. cylinder
Fd. 3 witnesses

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Left 3½" dia brass cap on conc. cylinder

1931 Witnesses: Cedar Post N 32.76' (33'R)
26" (22"R) White Pine N24°W 30.46' (30.40'R)
26" (22"R) White Pine N68°E 139.93' (139.75'R)

Set nail and tag PS #16041 in: Fence Cor Post S45°W 43.44'
16" White Pine S55°E 68.02'


REGISTER OF DEEDS
IOSCO COUNTY, MICH
Bruce H. Coyle

DEC 1 11 07 AM '93

FILED
93-43

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													



Signed by *James H. Granger*

Date Nov 30, 1993

Surveyor's Michigan License No. 16041