

**REMONUMENTATION CORNER  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Iosco</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T22N R7E</u>	<u>C-13</u>
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

STATE OF MICHIGAN  
IOSCO COUNTY  
FILED

3 DEC 97 11:48 A.M.

RONITA M. COYLE  
REGISTER OF DEEDS

**97-45**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, James H. Granger, in a field survey on August 4, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

1838	GLO	L. Clason	Set Wood Post	6" B. Ash	N13°W	15LKS
				8" B. Ash	N58°E	10LKS
1975	LCRC	James Campbell	#15397 set 1/2" pipe			
1975		James Campbell	#15397 1/2" pipe			
1991		James H. Granger	#16041 FD PK Rizer			

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

FD 1/2" Iron Pipe

Accept position as previously established.

ACCEPTED BY THE IOSCO COUNTY  
SURVEY PEER GROUP AS THE  
OFFICIAL CORNER UNDER P.A.  
345 OF 1990 AT A MEETING  
HELD ON 9-16-97

*James H. Granger*

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Set 5/8" rebar with Remon Cap in Mon Box.

Short utility pole	S50°W	44.82'	nail & tag 16041
3' tall utility pole	S21°E	56.77'	nail & tag 16041
3" Apple	N65°E	84.49'	nail & tag 16041
Road sign	N35°W	54.27'	
C-1 Remon Cap in Mon Box West		11.95'	(T21N, R7E)



Signed by *James H. Granger*  
Surveyor's Michigan License No. 16041

Date November 10, 1997

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975

REVISED JAN., 1983  
REVISED OCT., 1995

**SURVEY &  
REMONUMENTATION**

**MAR 18 1998**

**SECTION**