

**REMONUMENTATION CORNER  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Iosco</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T22N R7E</u>	<u>H-13</u>
	T <u>   </u> R <u>   </u>	<u>          </u>
	T <u>   </u> R <u>   </u>	<u>          </u>
	T <u>   </u> R <u>   </u>	<u>          </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>          </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>          </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>          </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>          </u>

STATE OF MICHIGAN  
IOSCO COUNTY  
FILED

3 DEC 97 11:50 A.M.

BONITA M. COYLE  
REGISTER OF DEEDS

**97-55**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, James H. Granger, in a field survey on August 4, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

1838 GLO L. Clason Set Wood Post 8" W. Birch N55°E 7LKS  
12" Tamarac N73°W 22LKS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found large PK nail  
Position agrees acceptably with single proportionate measurement between SW and SE Corners.  
Accept position as previously established.

ACCEPTED BY THE IOSCO COUNTY  
SURVEY PEER GROUP AS THE  
OFFICIAL CORNER UNDER P.A.  
345 OF 1990 AT A MEETING  
HELD ON 9-16-97

*James H. Granger*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" rebar with Remon Cap in Mon Box.

3" Aspen	N38°E	49.62'	nail & tag 16041
Utility Pole	S43°W	53.94'	nail & tag 16041
14" Aspen	N51°W	49.79'	nail & tag 16041
Road sign	S41°E	49.94'	
H-1 Remon Cap in Mon Box	S74°W	15.44'	(T21N, R7E)



Signed by James H. Granger  
Surveyor's Michigan License No. 16041

Date November 10, 1997

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975

REVISED JAN., 1983  
REVISED OCT., 1995

**SURVEY &  
REMONUMENTATION**

MAR 18 1998

SECTION