

**REMONUMENTATION CORNER  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
IOSCO COUNTY  
FILED

3 DEC 97 11:50 A.M.

RONITA M. COYLE  
REGISTER OF DEEDS

**97-57**

Register of Deeds Stamp & File Number

For corners in

|                                       |                   |               |
|---------------------------------------|-------------------|---------------|
| <u>Iosco</u><br>(County)              | Located In:       | Corner Code # |
| 1. Public Land Survey                 | <u>T22N R7E</u>   | <u>I-13</u>   |
|                                       | T ___ R ___       | _____         |
|                                       | T ___ R ___       | _____         |
|                                       | T ___ R ___       | _____         |
| 2. Property Controlling<br>in Section | S ___ T ___ R ___ | _____         |
|                                       | S ___ T ___ R ___ | _____         |
| 3. Miscellaneous<br>Property in Sec.  | S ___ T ___ R ___ | _____         |
|                                       | S ___ T ___ R ___ | _____         |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, James H. Granger, in a field survey on August 4, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

|    |    |   |    |   |    |   |    |   |    |   |    |   |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| A  | B  | C | D  | E | F  | G | H  | I | J  | K | L  | M |
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |

**A. Description of original monument and accessories and/or subsequent restoration:**

|      |      |                |               |   |       |       |
|------|------|----------------|---------------|---|-------|-------|
| 1838 | GLO  | L. Clason      | Set Wood Post | 10" W. Pine                               | N56°W | 14LKS |
|      |      |                |               | 36" W. Pine                               | N16°W | 72LKS |
| 1974 |      | Richard Miller | #16050        | 1" Iron                                   |       |       |
| 1974 |      | James Campbell | #15397        | 1" Iron Rod                               |       |       |
| 1977 | LCRC | Richard Miller | #16050        | 1" Iron                                   |       |       |
| 1980 |      | John Oliver    | #19840        | FD 1/2" pipe buried 12" raised w/3/8" Rod |       |       |
| 1988 |      | John Oliver    | #19840        | FD 3/8" rod                               |       |       |
| 1989 |      | John Oliver    | #19840        | FD 3/8" rod                               |       |       |

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found 1" iron pipe raised 1 ft by 3/8" rod  
Position agrees acceptably with simple proportionate measurements to the SW and SE Sec Corners.  
Accept position as previously established.

ACCEPTED BY THE IOSCO COUNTY  
SURVEY PEER GROUP AS THE  
OFFICIAL CORNER UNDER P.A.  
345 OF 1990 AT A MEETING  
HELD ON 9-16-97

*James H. Granger*

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Set 5/8" rebar with Remon Cap in Mon Box.

|                                     |       |        |                        |
|-------------------------------------|-------|--------|------------------------|
| 8" Box Elder                        | N20°E | 88.45' | fd 60 D spike w/ribbon |
| Utility Pole                        | S46°E | 44.91' | nail & tag 16041       |
| 10" Elm                             | S12°W | 64.72' | fd 60 D spike w/ribbon |
| magnetic PK, N. end 24" steel culv. | N53°W | 60.65' |                        |
| I-1 Remon Cap in Mon Box West       | 9.90' |        | (T21N, R7E)            |



Signed by James H. Granger  
Surveyor's Michigan License No. 16041

Date November 10, 1997

**SURVEY &  
REMONUMENTATION**

MAR 18 1998

SECTION