

**REMONUMENTATION CORNER  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Iosco	Located In:	Corner Code #
(County)		
1. Public Land Survey	T22N R7E	J-13
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN  
IOSCO COUNTY  
FILED

3 DEC 97 11:51 A.M.

RONITA M. COYLE  
REGISTER OF DEEDS

**97-59**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, James H. Granger, in a field survey on August 4, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1838	GLO	L. Clason	Set Wood Post	8" W. Pine 5" Maple	N90°W N44°E	23LKS 7LKS
1974		Richard Miller	#16050	RR Spike		
1974		James Campbell	#15397	PK Nail		
1977	LCRC	Richard Miller	#16050	FD PK Nail		
1980		John Oliver	#19840	FD PK Nail--set RR Spike		
1988		John Oliver	#19840	FD RR Spike		
1989		John Oliver	#19840	FD RR Spike		

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found RR spike. Position agrees with single proportionate distance between SW and SE Section Corners.  
Accept position as previously established.


ACCEPTED BY THE IOSCO COUNTY  
SURVEY PEER GROUP AS THE  
OFFICIAL CORNER UNDER P.A.  
745 OF 1990 AT A MEETING  
HELD ON 9-16-97

*James H. Granger*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" rebar with Remon Cap in Mon Box.

4" W. Pine	N58°E	86.23'	nail & tag 16041
5" Cedar Post	S12°W	38.84'	nail & tag 16041
8" Cottonwood	S71°W	95.26'	nail & tag 16041
Utility Pole	N41°W	99.33'	nail & tag 16041
J-1 Remon Cap in Mon Box	West	5.64'	(T21N, R7E)



Signed by James H. Granger  
Surveyor's Michigan License No. 16041

Date November 10, 1997

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975

REVISED JAN., 1983  
REVISED OCT., 1995

**SURVEY &  
REMONUMENTATION**

MAR 18 1998

SECTION