

REMONUMENTATION

MAY 07 1997

1996 IOSCO COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

90-36

For corners in

Iosco (County)	Located In:	Corner Code #
1. Public Land Survey	T 22N. R 8E	A-4
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
IOSCO COUNTY
FILED

5 NOV 96 4:27 P.M.

BONITA M. COYLE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, James H. Granger in a field survey on October 24, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1838 GLO Lewis Clason Set Wood Post
 11" Cedar S12°W 12 lks
 11" Cedar N65°W 17 lks

1988 Private Survey John Oliver #19840 Fd. iron in Mon. Box.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd. 1" pipe in Mon. box. No witnesses.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8"x30" rebar inside 1" pipe w/Remon. Cap in Mon. box.
 Center N. Side of bridge N60°W 35.90'
 Center S. Side of bridge S75°W 36.87'
 8" Elm S40°E 42.85'
 Fence post East 31.50'

ACCEPTED BY THE IOSCO COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 10-23-96

James H. Granger

nail & tag
nail & tag



CORNER ALSO LOCATED IN:
T22N R7E M-4

Signed by James H. Granger

Date October 28, 1996

Surveyor's Michigan License No. 16041