

SURVEY & REMONUMENTATION

MAY 07 1997

COMMISSION

**1996 IOSCO COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

20-40

For corners in

Iosco (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>8E</u>	<u>A-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
IOSCO COUNTY
FILED

5 NOV 96 4:29 P.M.

BONITA M. COYLE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, James H. Granger in a field survey on October 24, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1838 GLO Lewis Clason Set Wood Post 6" Tamarack S50°W 20 lks
10" Maple N34°W 29 lks
- 1975 Private Survey James Campbell #15397 1" rod in Mon. box.
- 1976 Private Survey Lloyd McGinnis #18999 Axle shaft in Mon. box.
- 1977 LCRC Lloyd McGinnis #18999 Axle shaft in Mon. box.
- 1994 Private Survey Richard Miller #16050 Indicates corner position.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd. 1" pipe in Mon. box. No witnesses.

ACCEPTED BY THE IOSCO COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER P.A.
345 OF 1990 AT A MEETING
HELD ON 10-23-96

James H. Granger

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 5/8"x30" rebar inside 1" pipe w/Remon. Cap in Mon. box.
- Utility pole N60°W 77.00' nail & tag
- 8" Oak S85°W 138.50' nail & tag
- Utility pole N75°E 42.37' nail & tag
- 10" W. Pine S55°E 115.63' nail & tag

CORNER ALSO LOCATED IN:
T22N R7E M-8



Signed by *James H. Granger*

Date October 28, 1996

Surveyor's Michigan License No. 16041