

# SURVEY & REMONUMENTATION

APR 27 1995

## COMMISSION

### IOSCO COUNTY REMONUMENTATION CORNER LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
IOSCO COUNTY  
FILED

15 NOV 94 4:05 P.M.

BONITA H. COYLE  
REGISTER OF DEEDS

For corners in

| Iosco<br>(County)                     | Located In:             | Corner Code ## |
|---------------------------------------|-------------------------|----------------|
| 1. Public Land Survey                 | T 22N R 8E              | A - 10         |
|                                       | T _____ R _____         | _____          |
|                                       | T _____ R _____         | _____          |
|                                       | T _____ R _____         | _____          |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____ | _____          |
|                                       | S _____ T _____ R _____ | _____          |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____ | _____          |
|                                       | S _____ T _____ R _____ | _____          |
| 4. Lot No. _____, Recorded Plat _____ |                         |                |
| 5. Private Claims _____               |                         |                |

94-17

Register of Deeds Stamp & File Number

I, James H. Granger, in a field survey on September, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

|                      |                                   |
|----------------------|-----------------------------------|
| 1843 Original Survey | Set Wood Post                     |
| John Mullett         | 12" Maple S50°W 27 lks            |
|                      | 12" Maple N71°W 3 lks             |
| 1868 Sub'd           | Map of Tawas City                 |
| 1959 Sub'd           | Huron Gardens Sub'd of Tawas City |

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**


Fd 1/2" pipe 8" below surface. Checked position against sub'd ties. Accepted position as found.

ACCEPTED BY THE IOSCO COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 10-10-94

*James H. Granger*

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

|   |                |
|---|----------------|
| Set 5/8" x 30" rebar with alum. cap in mon. box |                |
| Power Pole N48°E 48.71'                         | Set nail & tag |
| Power Pole S42°E 90.83'                         | Set nail & tag |
| Power Pole S55°W 135.43'                        | Set nail & tag |
| Power Pole N55°W 126.14'                        | Set nail & tag |



Signed by James H. Granger  
Surveyor's Michigan License No. 16041

Date November 10, 1994