

SURVEY & REMONUMENTATION

MAY 07 1997

COMMISSION

**1996 IOSCO COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

96-42

For corners in

<u>Iosco</u> (County)	Located In:	Corner Code #/
1. Public Land Survey	T <u>22N</u> R <u>8E</u>	<u>B-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
IOSCO COUNTY
FILED

5 NOV 96 4:28 P.M.

RONITA M. COYLE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, James H. Granger in a field survey on October 25, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3	7	8	9	10	11	12					
4	13	14	15	16	17	18					
5	19	20	21	22	23	24					
6	25	26	27	28	29	30					
7	31	32	33	34	35	36					
8											
9											
10											
11											
12											
13											

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1843 GLO John Mullett	Set Wood Post		
	6" Aspen	N14°W	10 lks
	6" Birch	S38°E	7 lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence found. Reestablished position by single proportionate measurement between SW and SE Sec. corners.

ACCEPTED BY THE IOSCO COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 10-23-96

James H. Granger

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8"x30" rebar w/Remon. cap			
24" Oak	S65°W	32.50'	nail & tag
12" Red Pine	N45°W	51.37'	nail & tag
10" Cedar	N20°E	42.50'	nail & tag
Power Pole #262	S35°E	71.55'	nail & tag



Signed by *James H. Granger*

Date October 28, 1996

Surveyor's Michigan License No. 16041