

**SURVEY &
REMONUMENTATION**

MAY 07 1997

**1996 IOSCO COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

COMMISSION

For corners in

96-52

Iosco (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>8E</u>	<u>E-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
IOSCO COUNTY
FILED

5 NOV 96 4:30 P.M.

RONITA M. COYLE
Register of Deeds, Stamp & File Number

I, James H. Granger in a field survey on October 25, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1843 GLO John Mullett Set Wood Post 10" Maple N 45° W 6 lks
8" B. Ash S 30° E 12 lks
- 1928 Sub'd John Applin #318 Indicates corner position
- 1960 Sub'd S.A. Tokoly Indicates corner position
- 1979 Private Survey Richard Miller #16050 Indicates corner position
- 1992 Private Survey Richard Miller #16050 Indicates corner position

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of previously established corners found. Road recently rebuilt. Reestablished corner position based on measurements from ex. subdivisions.

ACCEPTED BY THE IOSCO COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER P.A.
345 OF 1990 AT A MEETING
HELD ON 10-23-96

James H. Granger

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 5/8"x30" rebar w/Remon. Cap in Mon. box
- 8" Maple S 40° W 68.73' nail & tag
- 16" Oak N 20° W 87.49' nail & tag
- 12" Oak S 35° E 43.85' nail & tag
- 18" Oak N 55° E 68.20' nail & tag



Signed by James H. Granger

Date October 28, 1996

Surveyor's Michigan License No. 16041