

# SURVEY & REMONUMENTATION

APR 27 1995

## COMMISSION

### IOSCO COUNTY REMONUMENTATION CORNER LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
IOSCO COUNTY  
FILED

15 NOV 94 4:03 P.M.

BONITA M. COYLE  
REGISTER OF DEEDS

# 94-14

Register of Deeds Stamp & File Number

For corners in

Iosco  
(County)

Located In:

Corner Code ##

- |                                    |                         |       |
|------------------------------------|-------------------------|-------|
| 1. Public Land Survey              | T 22N R 8E              | E - 7 |
|                                    | T _____ R _____         | _____ |
|                                    | T _____ R _____         | _____ |
|                                    | T _____ R _____         | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
|                                    | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____ | _____ |
|                                    | S _____ T _____ R _____ | _____ |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, James H. Granger, in a field survey on September, 19 94

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- |                      |                        |
|----------------------|------------------------|
| 1843 Original Survey | Set Wood Post          |
| John Mullett         | 10" Cedar S16°E 14 lks |
|                      | 10" Cedar N24°W 13 lks |
| 1972 Sub'd           | Armel Acres            |
| 1978 Survey          | 1½" Pipe               |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1½" pipe bent over and previous witnesses of record. Removed bent pipe & set temporary point. Checked against witnesses and sub'd ties. Accepted position as established.

ACCEPTED BY THE IOSCO COUNTY  
SURVEY PEER GROUP AS THE  
OFFICIAL CORNER UNDER P.A.  
345 OF 1990 AT A MEETING  
HELD ON 10-10-94

*James H. Granger*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 5/8" x 30" rebar with alum. cap
- Gate Post N 34.65' Set nail & tag
- 6" Birch N60°W 41.10' Set nail & tag
- 8" Ash S50°W 72.78' Set nail & tag
- Conc. Mon. E 36.00'



Signed by James H. Granger

Date November 10, 1994

Surveyor's Michigan License No. 16041