

SURVEY & REMONUMENTATION

APR 27 1995

COMMISSION

**IOSCO COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
IOSCO COUNTY
FILED

15 NOV 94 4:03 P.M.

HONITA K. COYLE
REGISTER OF DEEDS

94-13

Register of Deeds Stamp & File Number

For corners in	Located In:	Corner Code #
<u>Iosco</u> (County)		
1. Public Land Survey	T <u>22N</u> R <u>8E</u>	<u>E - 8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, James H. Granger, in a field survey on September, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1843 Original Survey	Set Wood Post	1932 MDOT	1 1/2" pipe in 4" tile
John Mullett	18" Pine S6 1/2°E 99 lks	1975 Sub'd	Franklin Heights
	10" Pine N23°W 27 lks	1979 Survey	Conc. mon.
1880 Sub'd	Trustee's Add'n to Village of East Tawas		
1888 Sub'd	Emery Bros. Add'n to Village of East Tawas		

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Field search found 1/2" iron set and marked by Northeast Land Surveys. Found one previous witness of record. Check iron with sub'd ties. Accepted position as established.

ACCEPTED BY THE IOSCO COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 10-10-94

James H. Granger

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 30" rebar with alum cap
 conc. mon. S. 10.74'
 26" White Pine S60°W 92.12' set nail & tag
 10" White Pine E. 120.79' set nail & tag
 20" White Pine N20°W 81.37' set nail & tag



Signed by James H. Granger Date November 10, 1994
 Surveyor's Michigan License No. 16041