

**IOSCO COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

99-58

STATE OF MICHIGAN
IOSCO COUNTY
FILED

20 DEC 99 10:14 A.M.

RONITA M. COYLE
REGISTER OF DEEDS

For corners ...

<u> Iosco </u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>22NR 8E</u>	<u>G-6</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, JAMES H. GRANGER, in a field survey on April 27, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- | | | |
|------|--------------------------|--|
| 1843 | GLO
John Mullett | Set Wood Post 30" W. Pine N70°W 15lks
12" Hemlock S70°E 10lks |
| 1989 | Survey
Richard Miller | Set 1/2" rebar with cap. NO witnesses.
No LCRC filed |

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found Miller iron. Calculated position, based on measurement from established NW and SW corners is 0.69 ft. N and 0.26' E of Miller. Fd remains of W. Pine stump and possibly Hemlock stump. GLO witnesses will fit either position. Property surveys in Sec. 16 tied to Miller position. Dug in ground in area but did not find any evidence of GLO wood post. After diligent consideration accepted Miller position.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
G-6 W1/4 Sec. 15
Set 5/8" x 30" rebar with Remon Cap
8" Hemlock N10°W 21.80 nail & tag 16041
9" Red Oak N20°E 21.47' ex. 2" nail with red flagging
18" Ash S30°E 18.86' ex. 2" nail with red flagging
11" W. Birch N50°W 18.14' nail & tag 16041

ACCEPTED BY THE IOSCO COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER P.A.
348 OF 1990 AT A MEETING
HELD ON 10-13-99

James H. Granger



Signed by James H. Granger
Surveyor's Michigan License No. 16041

Date May 4, 1999

PER

APR 27 2000

SECTION