

SURVEY & REMONUMENTATION

APR 27 1995

COMMISSION

IOSCO COUNTY REMONUMENTATION CORNER LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
IOSCO COUNTY
FILED

For corners in

15 NOV 94 4:01 P.M.

BONITA K. COYLE
REGISTER OF DEEDS

94-08

Register of Deeds Stamp & File Number

<u>Iosco</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>8E</u>	<u>I - 7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, James H. Granger, in a field survey on September, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1843 Original Survey Set Wood Post
 - John Mullett 14" Yellow Pine S57°W 120 lks
 - 1931 MDOT US-23 road plans
 - 1949 Sub'd Woodland Park
 - 1959 Sub'd North Ridge No. 1
 - 1962 MDOT US-23 road plans

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- Found conc. monument and witnesses as previously recorded. Accepted position as established.

ACCEPTED BY THE IOSCO COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER P.A.
345 OF 1990 AT A MEETING
HELD ON 10-10-94

James H. Granger

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Concrete mon. with alum. cap
- 10" Jack Pine S5°E 12.58' Fd nail & ribbon
- 6" Twin Red Pine S75°E 18.29' Fd nail & ribbon
- 10" Red Pine N60°E 13.13' Fd nail & ribbon
- 10" Oak N16°W 20.71' Fd nail & ribbon



Signed by James H. Granger Date November 10, 1994

Surveyor's Michigan License No. 16041