

**SURVEY & REMONUMENTATION**

MAY 07 1997

COMMISSION

**1996 IOSCO COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Iosco</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>22N</u> R <u>8E</u>	<u>K-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

**96-54**

STATE OF MICHIGAN  
IOSCO COUNTY  
FILED

5 NOV 96 4:30 P.M.

RONITA W. COYLE  
Register of Deeds Stamp & File Number

I, James H. Granger, in a field survey on October 25, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

1843	GLO	John Mullett	Set Wood Post	10" Aspen	S 74° E	20 lks
				8" Aspen	S 70° W	20 lks
1922	Sub'd	John Applin	#318	Indicates corner position		
1927	Sub'd	John Applin	#318	Indicates corner position		
1941	Sub'd	R.J. Cooke	#2335	Indicates corner position		
1952	Sub'd	R.J. Cooke	#2335	Indicates corner position		
1972	LCRC	John Oliver	#19840	Indicates corner position		

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Fd. conc. monument which fits with measurements to ex. subdivisions.

ACCEPTED BY THE IOSCO COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 10-23-96

*James H. Granger*

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

4" dia x 48" conc. mon. with 1/2" rebar w/Remon. Cap			
Utility pole	N 65° E	28.22'	nail & tag
12" W. Pine	S 15° E	37.15'	nail & tag
12" W. Pine	S 70° W	21.98'	nail & tag
18" Oak	N 30° E	22.13'	nail & tag



Signed by James H. Granger Date October 18, 1996

Surveyor's Michigan License No. 16041