

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

**SURVEY &
REMONUMENTATION**

IOSCO COUNTY REMONUMENTATION

MAR 18 1998

Number of corners IOSCO Located In: _____ Corner Code # _____

SECTION

STATE OF MICHIGAN
IOSCO COUNTY
FILED

21 NOV 97 1:02 P.M.

RONITA M. COYLE
REGISTER OF DEEDS

97-33

Register of Deeds Stamp & File Number

Public Land Survey	T <u>23</u>	R <u>9</u>	B-13	
	T <u>22</u>	R <u>9</u>	B-1	
	T _____	R _____	_____	_____
	T _____	R _____	_____	_____
Property Controlling in Section	S _____	T _____	R _____	_____
	S _____	T _____	R _____	_____
Miscellaneous Property in Sec.	S _____	T _____	R _____	_____
	S _____	T _____	R _____	_____

Lot No. _____, Recorded Plat _____

Private Claims _____

WILLIAM E. WOODS P.S., in a field survey on NOV. 17, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 & 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by Decree of a Court of Law; established, re-established, monumented, recovered, found as crossed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:
 1843 ORIGINAL SURVEY SET WOOD POST
 J.F. MUNRO Y. PINE 8" DIAM. N 20° W, 22 LINKS
 Y. PINE 12" DIAM. N 12° S, 19 LINKS

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

ACCEPTED BY THE IOSCO COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 9-16-97

James H. Stranger

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1997 REMONUMENTATION WILLIAM E. WOODS FOUND NO EVIDENCE OF CORNER PROPOSE TO MEASURE TOTAL SOUTH SECTION LINE AND SET 1/4 CORNER AT PROPORTIONATE DISTANCE AS SHOWN ON 1963 SURVEY BY DAVID B. GAUTHRIE # 22435

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8 BAR AND REMON CAP MIDWAY ON LINE BETWEEN A0-13 AND C-13

- S 86° W 20" RED PINE 24.29'
- S 128 W 10" JACK PINE 31.66'
- N 67° E 10" TWIN RED PINE 24.12'
- N 06° W 8" RED PINE 10.68'
- 121.0' NORTH OF OLD ROAD

Witnessed by William E Woods Date 11-20-97
 WILLIAM E. WOODS P.S.

Surveyor's Michigan License No. 25882

