

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

95-26

For corners in

IOSCO (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>22</u> N <u>9</u> E	<u>B-3</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling In Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN  
IOSCO COUNTY  
FILED  
12 DEC 95 2:28 P.M.  
DONITA M. COBLE  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, WILLIAM E. WOODS in a field survey on 10-24, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:  
1843 ORIGINAL SURVEY, JOHN MULLETT SET WOOD POST  
8" SPRUCE PINE S76°E 27LK  
6" SPRUCE PINE N58°W 66LK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
1972 SURVEY, JAMES G. CABBELL #15397 INDICATES CORNER IS L.223 P. 706  
1/2 PIPE WITH CAP  
S 45°E 10" J. PINE 23.87  
N 85°W 10" J. PINE 18.83

ACCEPTED BY THE IOSCO COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 10-31-95  
*James H. Granger*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
1995 REMONUMENTATION, WILLIAM E. WOODS FOUND PIPE 1/2" AND REPLACED WITH 5/8 X 30" REROD AND ALUMINUM CAP  
8" OAK S190°W 26.10  
12" OAK S109°E 33.11  
UTILITY POLE N58°E 65.20  
10" CEDAR CORNER POST N02°E 47.40



Signed by William E Woods  
Surveyor's Michigan License No. 25882

Date 12-8-95