

**IOSCO COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
IOSCO COUNTY
FILED

For corners in

5 DEC 94 2:01 P.M.

<u>IOSCO</u> <small>(County)</small>	Located In:	Corner Code #/
1. Public Land Survey	T <u>22N</u> R <u>9E</u>	<u>C-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

BONITA N. COYLE
REGISTER OF DEEDS

94-37

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John F. Oliver, in a field survey on September 12, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	I
2	6	•	5	4	3	2	1					
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1843 Original Survey, J.F. Munro Set Wood Post
4" S. Pine N14°E 20 links
6" S. Pine S23°W 25 links

1983 Survey by William E. Woods, P.S. indicates found 1-1/4" Pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Accept position as established by William E. Woods, P.S. Survey

Found 1-1/4" Iron pipe


ACCEPTED BY THE IOSCO COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER P.A.
345 OF 1990 AT A MEETING
HELD ON 11-10-94

James H. Granger

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" re-bar in 1-1/4" pipe, with aluminum cap

8" Jackpine N81°W 11.43
8" Oak N81°W 31.27
8" Oak (closest of 5 multi-oak) N51°E 58.22
6" Jack pine S5°E 17.71



Signed by _____ SURVEY & _____
Surveyor's Michigan License No. 19840 REMONUMENTATION

11-11-94

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN. 1983

SEP 22 1999

SECTION