

FEB 2 9 1996

IOSCO COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

95-15

For corners in

IOSCO
(County)

Located In:

Corner Code #

Public Land Survey

T23N R 5E

K-7

T R

T R

T R

Property Controlling
in Section

S T R

S T R

Miscellaneous
Property in Sec.

S T R

S T R

Lot No. , Recorded Plat

Private Claims

James H. Granger, in a field survey on November 7, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1844 Original Survey Wood Post
24" Hemlock N57°W 4 lks.
20" Hemlock S1°E 41 lks

1990 Private Survey found 5/8" sq. boat spk.
1992 Private Survey

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" sq. boat spike and witness previously established.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" x 30" rebar with aluminium cap

PP N55°W 87.75' ex. spike
4"x4" Telephone Post N45°E 44.02' set nail and tag
Fence Post S40°W 56.19' set nail and tag
PP S30°E 140.86' set nail and tag

"X" in bolt, E side of SE leg of steel elec. tower N14°W 156.29'

Signed by James H. Granger
Surveyor's Michigan License No. 16041

Date December 6, 1995

STATE OF MICHIGAN
IOSCO COUNTY
FILED

12 DEC 95 2:22 P.M.

BOHITA M. COYLE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

ACCEPTED BY THE IOSCO COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER P.A.
345 OF 1990 AT A MEETING
HELD ON 10-31-95

James H. Granger

