

# SURVEY & REMONUMENTATION

APR 27 1995

## IOSCO COUNTY REMONUMENTATION CORNER LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
IOSCO COUNTY  
FILED

### COMMISSION

For corners in

15 NOV 94 4:07 P.M.

BONITA M. COYLE  
REGISTER OF DEEDS

94-19

Register of Deeds Stamp & File Number

Iosco (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>23</u> N R <u>8E</u>	<u>B - 9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9	●												
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, James H. Granger, in a field survey on September, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
1843 Original Survey Corner was 16" Cedar  
John Mullett

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Field search found boatspike. Source unknown. Local surveyors have used and accepted.  
Road Commission has accepted position. Accepted position as found.

ACCEPTED BY THE IOSCO COUNTY  
SURVEY PEER GROUP AS THE  
OFFICIAL CORNER UNDER P.A.  
345 OF 1990 AT A MEETING  
HELD ON 10-10-94

*James H. Granger*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 30" rebar in mon. box

Power Pole	S70°W	42.56'	Set nail & tag
Power Pole	S65°E	73.22'	Set nail & tag
Power Pole	N30°E	80.71'	Set nail & tag
8" Cedar	N65°W	33.19'	Set nail & tag



Signed by James H. Granger Date November 10, 1994

Surveyor's Michigan License No. 16041