

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

IOSCO COUNTY REMONUMENTATION

For corners IOSCO Located In: _____ Corner Code # _____

1. Public Land Survey	T <u>23</u>	R <u>9</u>	A-1
	T <u>24</u>	R <u>9</u>	A-13
	T <u>24</u>	R <u>8</u>	M-13
	T <u>23</u>	R <u>8</u>	M-1 ✓
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

STATE OF MICHIGAN
IOSCO COUNTY
FILED

21 NOV 97 1:08 P.M.

RONITA N. COYLE
REGISTER OF DEEDS

97-40

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, **WILLIAM E. WOODS P.S.**, in a field survey on NOV. 17, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 1837 SURVEY BY SET WOOD POST
 LEWIS CLASON, DS 18" Y. PINE S 83° W, 42 LINKS
 6" SPRUCE PINE N 65° S, 61 LINKS

ACCEPTED BY THE IOSCO COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 9-16-97

James H. Strange

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1908 W. G. FARGO SURVEY FOUND 1 1/4" PIPE BELOW SURFACE, 2 RED CLAY BRICKS, IRON CUTTER SHOE, 4" SQUARE ROTTED PINE STAKE, NO WITNESSES WERE TAKEN
 1960 GEORGE BLASS SURVEY PLACED 30 LB. SPIKE WITH WASHER IN CENTER LINE OF ROAD, CIRCULAR 6" X 5' LONG REINFORCED CONCRETE REF. MONUMENT 18" ABOVE GROUND 33' DUE NORTH OF RECOVERED CORNER POINT. MONUMENT CAPPED BY 3 1/2" BRASS PLATE
 10" JACK PINE N41°30' E, 69.83' SCRIBED BT 31
 8" BLACK OAK S 17° E 119.47' SCRIBED BT 6
 9" BLACK OAK N 29° W 84.63' SCRIBED BT 36

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner
 FOUND 1 1/4" PIPE AT CORNER AND BRASS PLATE 33.05' S OF CORNER REPLACED 1 1/4" PIPE WITH 5/8 ROD AND REMON CAP

10" JACK PINE N66° E 69.96' BT 31
 2" BLACK OAK S 35° E 62.42' TO SPIKE
 9" BLACK OAK N 23° W 84.63'
 2" BLACK OAK S 57° W 72.57' TO NAIL AND TAG

Signed by William E Woods Date 11-20-97

WILLIAM E. WOODS P.S.

Surveyor's Michigan License No. 25882



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

SURVEY & REMONUMENTATION

MAR 18 1998

SECTION