

**LAND CORNER RECORDATION CERTIFICATE**

**SURVEY & REMONUMENTATION**

**Filing Requirement of Act 74, Mich. P.A. 1970**

IOSCO COUNTY REMONUMENTATION

MAR 18 1998

For corners IOSCO Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey  
 T 23 R 9 A-2  
 T 23 R B M-2  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

SECTION

STATE OF MICHIGAN  
 IOSCO COUNTY  
 FILED

21 NOV 97 1:07 P.M.

RONITA H. COYLE  
 REGISTER OF DEEDS

**97-39**

Register of Deeds Stamp & File Number

5. Private Claims \_\_\_\_\_

I, WILLIAM E. WOODS P.S., in a field survey on NOV. 17, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1843 ORIGINAL SURVEY SET WOOD POST  
 J.F. MUNRO RED OAK 7" DIAM. S 21° W 53 LINKS  
 Y. PINE 18" DIAM. N 61° W 175 LINKS

ACCEPTED BY THE IOSCO COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 9-16-97

*James H. Granga*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

NO EVIDENCE OF CORNER FOUND  
 PROPOSE TO SET AT SINGLE  
 1997 REMONUMENTATION PROPORTIONATE DISTANCE BETWEEN  
 WILLIAM E. WOODS REMOND CORNERS A-1 AND A-3

C. Description of monument for corner and accessories established to perpetuate locating the position of the come

SET 5/8 ROD AND REMON CAP MIDWAY BETWEEN A-1 AND A-3  
 N 61° W 6" TWIN OAK 51.73'  
 S 87° W 4" OAK 52.26'  
 S 02° W 4" JACK PINE 19.96'  
 N 15° E 4" JACK PINE 10.60'  
 23.60' EAST OF MEAD ROAD CENTERLINE



Signed by William E Woods

Date 11-20-97

WILLIAM E. WOODS P.S.

Surveyor's Michigan License No. 25882