

LAND CORNER RECORDATION CERTIFICATE

SURVEY & REMONUMENTATION

Filing Requirement of Act 74, Mich. P.A. 1970

IOSCO COUNTY REMONUMENTATION

MAR 18 1998

For corners IOSCO Located In: _____ Corner Code # _____

1. Public Land Survey T 23 R 9 A-2
 T 23 R 8 M-2
 T _____ R _____
 T _____ R _____
 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

SECTION

STATE OF MICHIGAN
 IOSCO COUNTY
 FILED

21 NOV 97 1:07 P.M.

RONITA M. COYLE
 REGISTER OF DEEDS

97-39

Register of Deeds Stamp & File Number

I, WILLIAM E. WOODS P.S., in a field survey on NOV. 17, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1843 ORIGINAL SURVEY SET WOOD POST
 J.F. MUNRO RED OAK 7" DIAM. S 21° W 53 LINKS
 Y. PINE 18" DIAM. N 61° W 175 LINKS

ACCEPTED BY THE IOSCO COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 9-16-97

James H. Granga

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

NO EVIDENCE OF CORNER FOUND
 PROPOSE TO SET AT SINGLE
 1997 REMONUMENTATION PROPORTIONATE DISTANCE BETWEEN
 WILLIAM E. WOODS REMOND CORNERS A-1 AND A-3

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner
 SET 5/8 ROD AND REMON CAP MIDWAY BETWEEN A-1 AND A-3

N 61° W 6" TWIN OAK 51.73'
 S 87° W 4" OAK 52.26'
 S 02° W 4" JACK PINE 19.96'
 N 15° E 4" JACK PINE 10.60'
 23.60' EAST OF MEAD ROAD CENTERLINE

Signed by William E Woods

Date 11-20-97

WILLIAM E. WOODS P.S.

Surveyor's Michigan License No. 25882

