

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
 IOSCO COUNTY REMONUMENTATION

For corners IOSCO Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey	T	23	R	9	<u>A-5</u>
	T	<u>23</u>	R	<u>9</u>	<u>M-5</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Sec.	S	_____	T	_____	R
	S	_____	T	_____	R
4. Lot No. _____, Recorded Plat _____					
5. Private Claims _____					

STATE OF MICHIGAN  
 IOSCO COUNTY  
 FILED

21 NOV 97 1:04 P.M.

BONITA M. COYLE  
 REGISTER OF DEEDS

**97-37**

Register of Deeds Stamp & File Number

I, WILLIAM E. WOODS P.S., in a field survey on NOV. 17, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1843 ORIGINAL SURVEY  
 J.F. MUNRO

SET WOOD POST  
 WHITE PINE 10" DIAM. S 75° W, 14 LINKS  
 WHITE PINE 9" DIAM. N 70° W, 13 LINKS

ACCEPTED BY THE IOSCO COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 343 OF 1990 AT A MEETING HELD ON 9-16-97

*James H. Stranger*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1997 REMONUMENTATION  
 WILLIAM E. WOODS

FOUND R. L. MILLER BAR AND CAP AT CORNER POSITION  
 PROPOSE TO USE MILLER CORNER AS ESTABLISHED

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner

FOUND R.L. MILLER 1/2" BAR AND CAP, REPLACED WITH 5/8 ROD AND REMON CAP

S 20° W 31.05' 12" RED PINE, SET NAIL AND TAG IN BLAZE  
 S 14° E 47.00' 18" RED PINE, SET NAIL AND TAG IN BLAZE  
 N 47° W 17.63' 8" RED PINE, SET NAIL AND TAG IN BLAZE  
 N 33° E 30.0' 8" RED PINE, SET NAIL AND TAG IN BLAZE

CORNER IS SOUTH 17.3' OF TRAIL CENTER LINE

Signed by William E Woods  
 WILLIAM E. WOODS P.S.

Date 11-20-97

Surveyor's Michigan License No. 25882



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983

**SURVEY &  
 REMONUMENTATION**

MAR 18 1998

SECTION