

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

IOSCO COUNTY REMONUMENTATION

For corners IOSCO Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey      T 23    R 9      B-3  
    T \_\_\_\_\_ R \_\_\_\_\_  
    T \_\_\_\_\_ R \_\_\_\_\_  
    T \_\_\_\_\_ R \_\_\_\_\_
2. Property Controlling    S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    in Section                S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
3. Miscellaneous            S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    Property in Sec.        S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
 IOSCO COUNTY  
 FILED

21 NOV 97 1:03 P.M.

RONITA M. COYLE  
 REGISTER OF DEEDS

**97-34**

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3	•												
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, WILLIAM E. WOODS P.S., in a field survey on NOV. 17, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

1843 ORIGINAL SURVEY	SET WOOD POST
J. F. MUNRO	WHITE PINE 26" DIAM. S 41° E, 24 LINKS
	WHITE PINE 18" DIAM. N 25° W, 25 LINKS

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

1997 REMONUMENTATION	FOUND 1/2" REROD 2639.2 0' W OF SE CORNER OF SEC. 6 (C-3)
WILLIAM E. WOODS	AND 2792.53' E OF SW CORNER OF SEC. 6 (A-3)
	FOUND 1/2" REROD ON LINE BETWEEN C-3 AND A-3

PROPOSE TO SET 1/4 CORNER AT PROPORTIONATE DISTANCE OR  
 MIDWAY BETWEEN C-3 AND A-3 OR 76.67' W OF FOUND REROD

**C. Description of monument for corner and accessories established to perpetuate locating the position of the come**

SET 5/8 BAR AND REMON CAP IN MONUMENT BOX

- N 27° W 4" JACK PINE 50.26'
- S 15° W 8" JACK PINE 43.08'
- S 34° E 10" JACK PINE 49.66'
- N 60° E 3" JACK PINE 63.69'

Signed by William E Woods Date 11-20-97  
 WILLIAM E. WOODS P.S.

Surveyor's Michigan License No. 25882



**SURVEY &  
 REMONUMENTATION**

MAR 18 1998

SECTION

FORM APPROVED BY MICHIGAN STATE  
 BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983