

**IOSCO COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

**96-75**

For corners in  
IOSCO  
(County)

Located In: Corner Code #

- |                                    |                          |            |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey              | T <u>23N</u> R <u>9E</u> | <u>C-1</u> |
|                                    | T _____ R _____          | _____      |
|                                    | T _____ R _____          | _____      |
|                                    | T _____ R _____          | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____  | _____      |
|                                    | S _____ T _____ R _____  | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____  | _____      |
|                                    | S _____ T _____ R _____  | _____      |

STATE OF MICHIGAN  
IOSCO COUNTY  
FILED

6 DEC 96 2:12 P.M.

BONITA M. COYLE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, WILLIAM E. WOODS in a field survey on NOVEMBER 19, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1843: ORIGINAL GOVERNMENT SURVEY SET POST CORNER 52 LINKS EAST OF POST 10" PINE S81°W, 40 LINKS, 12" PINE S48°E, 43 LINKS
- 1947: R.J. COOKE TATE'S PINECREST SHOWS COMMON CORNERS WEST PLAT BOUNDARY, IN ERROR. CORNER SHOWN ON PLAT IS SOUTHWEST CORNER OF SECTION 32, C-13, T24N, R9E.
- 1987: GOURDIE / FRASER & ASSOCIATES BOUNDARY SURVEY ON W.A.F.B. PROVES THIS CORNER TO BE 34.61 EAST OF CORNER SHOWN ON PLAT.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**


- 1996: WILLIAM E. WOODS FOUND 1" PIPE 34.61 EAST OF SOUTHWEST CORNER OF SECTION 31, T23N, R9E, REPLACED 1" PIPE WITH 5/8 ROD AND ALUMINUM CAP.

ACCEPTED BY THE IOSCO COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 10-23-96

*James H. Cranger*

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- 5/8 ROD WITH ALUMINUM CAP  
P.P. S11°W 54.43  
P.P. N38°W 50.08  
P.P. N52°E 42.99  
TRIPLE 8" RED PINES S15°E 44.66



Signed by William E Woods Date NOVEMBER 19, 1996  
Surveyor's Michigan License No. 25882

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

**SURVEY &  
REMONUMENTATION**

SEP 22 1996

SECTION