

# LAND CORNER RECORDATION CERTIFICATE

## Filing Requirement of Act 74, Mich. P.A. 1970

IOSCO COUNTY REMONUMENTATION

For comers IOSCO Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey	T	<u>23</u>	R	<u>9</u>	C-4
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T		R
	S		T		R
3. Miscellaneous Property in Sec.	S		T		R
	S		T		R
4. Lot No. _____, Recorded Plat _____					
5. Private Claims _____					

STATE OF MICHIGAN  
IOSCO COUNTY  
FILED

21 NOV 97 1:02 P.M.

RONITA H. COYLE  
REGISTER OF DEEDS

# 97-32

Register of Deeds Stamp & File Number

I, WILLIAM E. WOODS P.S., in a field survey on NOV. 17, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

1843 ORIGINAL SURVEY	SET WOOD POST
J.F. MUNRO	WHITE PINE 16" DIAM. N 30° E, 21 LINKS
	WHITE PINE 14" DIAM. S 50° W, 8 LINKS

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

1997 REMONUMENTATION	NO EVIDENCE OF CORNER
WILLIAM E. WOODS	TO SET BY SINGLE PROPORTIONATE BETWEEN C-3 AND C-5

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

SET 5/8 REROD AND REMON CAP MIDWAY AND ON LINE BETWEEN C-3 AND C-5

- N 88° E 11.28' 14" RED PINE, SET NAIL AND TAG IN BLAZE
- N 25° E 7.58' 14" RED PINE, SET NAIL AND TAG IN BLAZE
- N 40° W 11.23' 12" RED PINE, SET NAIL AND TAG IN BLAZE
- N 50° E 37.98' 8" RED PINE, SET NAIL AND TAG IN BLAZE

Signed by William E Woods Date 11-20-97  
 WILLIAM E. WOODS P.S.  
 Surveyor's Michigan License No. 25882

ACCEPTED BY THE IOSCO COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1993 AT A MEETING HELD ON 9-16-97

*James H. Granger*

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													



**SURVEY &  
REMONUMENTATION**

MAR 18 1998

SECTION

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983