

# LAND CORNER RECORDATION CERTIFICATE

## Filing Requirement of Act 74, Mich. P.A. 1970

IOSCO COUNTY REMONUMENTATION

For corners IOSCO Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey		T	<u>23</u>	R	<u>9</u>		E-4	
		T	_____	R	_____		_____	
		T	_____	R	_____		_____	
		T	_____	R	_____		_____	
2. Property Controlling in Section	S	_____	T	_____	R	_____	_____	_____
	S	_____	T	_____	R	_____	_____	_____
3. Miscellaneous Property in Sec.	S	_____	T	_____	R	_____	_____	_____
	S	_____	T	_____	R	_____	_____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
IOSCO COUNTY  
FILED

21 NOV 97 12:47 P.M.

RONITA M. COYLE  
REGISTER OF DEEDS

# 97-29

Register of Deeds Stamp & File Number

I, **WILLIAM E. WOODS P.S.**, in a field survey on NOV. 17, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1843 ORIGINAL SURVEY	SET WOOD POST
J.F. MUNRO	W. PINE 30" DIAM. S 21° E, 21 LINKS
	W. BIRCH 12" DIAM. N 52° W, 18 LINKS

ACCEPTED BY THE IOSCO COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 9-16-97

*James H. Stranger*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1997 REMONUMENTATION	FOUND 5/8 ROD AT DISTANCE SHOWN ON R.L. MILLER SURVEY
WILLIAM E. WOODS	

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

FOUND 5/8 BAR SET REMON CAP

S 52° W TRIPLE 12" BIRCH 20.14'  
S 11° E 18" MAPLE 60.53'  
N 45° E 24" W. PINE 59.61'  
N 16° W 8" ASH 48.42'

Signed by William E Woods Date 11-20-97

WILLIAM E. WOODS P.S.

Surveyor's Michigan License No. 25882



**SURVEY &  
REMONUMENTATION**

MAR 18 1998

SECTION

FORM APPROVED BY MICHIGAN STATE  
BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983